

Estimate of Quantities

| Sr. | Description of the work | Quantity | Cement | Sand (cu m) | Aggregate (cu m) | Brick | Steel in kg | Moorum (cu m) |
|-----|-------------------------|--------------|-----------------|----------------|---------------------|--------|----------------|------------------|
| 1 | M-10 grade CC | 37.062 cu.m | 5.633 | 16.9 | 33.8 | 0 | 0 | 0 |
| 2 | M-20 CC | 64.142 cu.m | 17.726 | 26.589 | 53.178 | 0 | 0 | 0 |
| 3 | Steel | 6295 kg | 0 | 0 | 0 | 0 | 6295 | 0 |
| 4 | Brick work | 165.886 cu.m | 11.059 | 66.353 | 0 | 107850 | 0 | 0 |
| 5 | Plaster | 1426.586sq.m | 4.754 | 28.52 | 0 | 0 | 0 | 0 |
| 6 | Hard moorum | 129.96 cu.m | 0 | 0 | 0 | 0 | 0 | 129.96 |
| | | Total | 39.172 | 138.362 | 86.978 | 107850 | 6295 | 129.96 |
| | | | or 1097 bags | | | | | |

Sunil Agarwal
Conservator of Forests,
Working Plan, Balaghat